

## **ADDENDUM NO. 5:**

Date: October 8, 2014  
Project: Salvation Army Center of Hope  
Owner: The Salvation Army  
Architect: Ward Scott Architecture

### **1.1 GENERAL:**

- A. **Clarification;** All wood roof decking to be 3/4" sheathing.
- B. **Clarification; Sheet S004 Typical Masonry Jamb Detail;** For openings less than or equal to 7'-0" wide, provide a single #5 bar on either side of opening for typical masonry jambs. For openings 7'-0" to 12'-0" wide, provide a #5 bar in two cells on each side of the door (for a total of 4 bars). Please note, where beams are supported additional bars are required as illustrated on sheet S004, CMU Lintel Elevation.
- C. **Clarification;** Provide three Salvation Army signs as shown in detail 5/A002. Two to be illuminated exterior signage and one to be non-illuminated interior signage.

### **1.2 SPECIFICATIONS:**

- A. **Section 074213.16; Metal Plate Wall Panels;** para. 2.2.A ; add the words "or equal"
- B. **Section 074213.16; Metal Plate Wall Panels;** para. 2.2.B ; delete this paragraph
- C. **Section 101416; Plaques;** para. 2.1.A ; delete this paragraph
- D. **Section 101419; Dimensional Letter Signage;** para. 2.1.A ; delete this paragraph
- E. **Section 101423; Panel Signage;** para. 2.1.A ; delete this paragraph

**END OF ADDENDUM**