TALA Professional Services

1116 20th Street South #306
Birmingham, Alabama 35205
205-578-1993 (p)
205-369-3406 (c)
www.talapro.com

ADDENDUM-1

TO: Bidders on the The Gateway Project
AV Hardware and Installation (A15-1488)
City of Tuscaloosa

FROM: Tim Lewis, TALA Professional Services

SUBJECT: The Gateway Project
AV Hardware and Installation – Addendum-1

DATE: January 18, 2016

Important Information

New Bid Opening Date: January 28, 2016 at 3:00pm at Tuscaloosa City Hall
Replace the Unit Pricing Sheet with a "Revised" Copy
Replace TALA Pro AV Dwg 1 with a "Revised" Copy of Dwg 1

TALA Professional Services (TALA) has developed the following answers to inquires regarding the The Gateway – AV System Hardware and Installation.

Group A Questions

1. Sharp has discontinued the LC-50Le650 and LC-32E67U I would recommend NEC as replacement for commercial grade with rs-232 control.

Answer: The NEC, Samsung ED Series and the LG LX are approved substitute for the discontinued Sharp. Any substitute must have an RS-232 control port.

2.   Cables to go has discontinued the C3G

Answer: Replace the Cable-To-Go C3G with an Altinex TNP328S. These units are to be mounted onto the owner furnished work tables (2) in Work Lounge 2.

3.   The quantity of parts for the displays and Crestron parts is different on the Unit Price Sheet, the AV Line Diagram, and the official Bid Specifications. All have different quantities.

Answer: In the bid document pg 8, 1.26 Input Cards for Switcher, Quantities should be corrected to read as follows: DMC-4K-HD (Qty 6), DMC-4K-C (Qty 9) and DMC-STR (Qty 1). The DMC-STR is to replace one of the DMC-4K-C that is on the drawings.

4.   The 42" LG displays are omitted from the AV Line Diagram

Answer: In bid document pg 9, 2.18 Monitors for Work Lounge 2 Table Monitors are to be attached to furniture provided by Owner and are not part of the Crestron MD 16x16 switcher. These monitors will only to have a local inputs using the Altinex TMP238S at each table (refer to question 2). See Attachment Drawing A.

5.   The line diagram shows the button panel connecting to the control system over cat6 and it is a Cresnet device.

Answer: The Crestron Keypad C2N-CBD-P should be connected to the Cresnet port on the CP3N using the appropriate cabling. Please review attached revised drawings.

6.   The wireless touch panels require wireless gateways. They do not work over Wifi.

Answer: Add one (1) Crestron CEN-RFGW-EX gateway. Add one (1) C2N-HBLOCK. Please review attached drawings

Additional Changes and Comments

1. **In Bid Document pg 8, 2.18 Monitors for Work Lounge 2. Change the size of wall mounted TV monitor from 50" to 42".**

2. **In Bid Document pg 11, 1.32 Low Voltage Control for Shades. Please delete all 4 units.**

3. **In Bid Document pg 10, 1.23 House control system. Replace the Crestron CP3 with the Crestron CP3N.**

4. **In Bid Document, page 9, 2.19. Monitor for Coffee Shop. Change the size of wall mounted monitor for 50" to 42".**

All questions regarding this bid and addendum should be directed to Tim Lewis, tlewis@talapro.com, 205-369-3406 cell.